

**AGENDA**  
**PUBLIC WORK'S COMMITTEE MEETING**  
**Wednesday, September 9<sup>th</sup>, 2020**  
**5:30 P.M., Allouez Village Hall**  
**\*Virtual Meeting\***

**NOTE:** Due to the COVID-19 pandemic, interested parties and the media can access the meeting via phone at:

(312) 626-6799  
Meeting ID: 935 3016 0960  
Password: 019748

1. MODIFY/ADOPT AGENDA
2. PUBLIC APPEARANCES  
(Any person wanting to provide input on any agenda item or other topic may provide those comments via email to [debbie@villageofallouez.com](mailto:debbie@villageofallouez.com) by 5:00 pm Tuesday, 9/08/2020, and that those comments would be read into the record during the Public Comment section of the agenda.)

**NEW BUSINESS:**

3. DISCUSSION/ACTION: BROWN COUNTY MUNICIPAL RECYCLING AGREEMENT (DPW Gehin).

**DISCUSSION/REPORT:**

4. DISCUSSION/REPORT: HIRING OF A NEW ENGINEERING TECHNICIAN (DPW Gehin)
5. DISCUSSION/REPORT: HWY 172 SPEED STUDY – WDOT COLLECTED DATA (DPW Gehin)
6. DISCUSSION/REPORT: 2020 CONSTRUCTION PROJECT UPDATE (DPW Gehin)
7. ADJOURNMENT

**NOTE:** It is possible that members of and a possible quorum of members of other governmental bodies of the municipality may be in attendance at the above noticed meeting to gather information; no action will be taken by any governmental body at the above noticed meeting other than the governmental body specifically referred to above in this notice.

# VILLAGE OF ALLOUEZ

Allouez Village Hall ◦ 1900 Libal Street ◦ Green Bay, Wisconsin 54301-2453  
Phone No.: (920) 448-2800 ◦ Fax No.: (920) 448-2850

## Department of Public Works

### BROWN COUNTY MUNICIPAL RECYCLING AGREEMENT

The Village of Allouez on an annual basis applies for a DNR recycling grant. In 2020 the Village received approximately \$98,000 from the program. To be eligible for the grant a signed cooperative agreement with other communities for the consolidation of recycling services including education and outreach, transport of recyclables, and comprehensive planning is required. Signature of the attached Brown County Municipal Recycling Agreement amendment will ensure our eligibility for the 2021 recycling grant.

The grant application is due October 1<sup>st</sup>.

**BROWN COUNTY MUNICIPAL RECYCLING  
AGREEMENT AMENDMENT XI**

This amendment is intended to reaffirm the existing language set forth in the Municipal Recycling Agreement in order to establish eligibility for the 2021 Wisconsin Recycling Consolidation Grant.

The existing agreement is a cooperative agreement for the joint provision of recycling services including education and outreach, collection and transport of recyclables to a materials recovery facility, and performing comprehensive program planning.

The following Brown County Municipalities recognize the fact that they are Partner Communities with Brown County in the Municipal Recycling Agreement:

City of Green Bay	Town of Green Bay
City of DePere	Town of Holland
Village of Allouez	Town of Humboldt
Village of Ashwaubenon	Town of Lawrence
Village of Bellevue	Town of Ledgeview
Village of Hobart	Town of Pittsfield
Village of Howard	Town of Rockland
Village of Pulaski	Town of Scott
Village of Suamico	Town of Wrightstown
Village of Wrightstown	Oneida Nation

**Village of Allouez**

By: \_\_\_\_\_

By: \_\_\_\_\_

Its: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

Dated: \_\_\_\_\_

**BROWN COUNTY**

By: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

Preliminary Speed Data

# WIS 172 Speed Survey Request Village of Ashwaubenon and Village of Allouez

WisDOT has made numerous observations of the WIS 172 segment near Webster Avenue and the existing 55/65 regulatory speed zone change near Libal Street during the past three years. Observations indicate that semi noise from accelerating and braking are predominately taking place at the Webster Avenue interchange ramps (westbound WIS 172 offramp to Webster and Webster to eastbound WIS 172 on ramp) and not the 55/65 mph regulatory speed limit change near Libal Street. Based on these observations a change in location of the 55/65 regulatory speed limit would not reduce truck noise in the area.

85th Percentile: 65 mph  
Average: 61 mph

85th Percentile: 65 mph  
Average: 60 mph

85th Percentile: 70 mph  
Average: 62 mph

85th Percentile: 73 mph  
Average: 70 mph

For comparison, data will also be collected on WIS 172 west of IH 41 and east of County GV/Monroe Road

★ Locations of speed data collection

Preliminary Speed Data Google Earth

© 2018 Google

# VILLAGE OF ALLOUEZ

Allouez Village Hall • 1900 Libal Street • Green Bay, Wisconsin 54301-2453  
Phone No.: (920) 448-2800 • Fax No.: (920) 448-2853

## Department of Public Works

### 2020 Public Works Projects -Schedule

September 4<sup>th</sup>, 2020

This 2020 construction season has begun in The Village of Allouez, some or all of the Public Works Projects are listed below:

1. St Mary's Boulevard -- Riverside Dr to ± 1500 feet to east (#310/#311)
2. Stanton Court/Arbor Lane -- Stanton Ct to Rosemont Dr (near Webster Ave)
3. Garland Street - Webster Ave to Baird St
4. Allouez Terrace Alley - Riverside Dr to end.
5. East St Joseph Alley - behind Associated Bank
6. Olde River Condominium Trail
7. Longview Pond Trail Repair
8. Bethel Pond Project
9. Standpipe (Water Tower) Repair Project

These street improvements include:

- Removal and replacement of the asphalt pavement.
- Replacement of defective gravel base
- Replacement of defective concrete curb & gutter and driveway aprons
- Manhole & catch basin repairs
- Sanitary sewer repairs on St Mary's Blvd

#### **1. St Mary's Boulevard - Riverside Dr to ± 1500 feet to east (#310/#311)**

Weather permitting the anticipated project schedule is as follows:

- Work started - May 7
- Completion Date - October 30<sup>th</sup>, 2020

Project Status:

The CIPP lining of the Sanitary sewer mainline was completed the week of August 10<sup>th</sup>. Sanitary sewer lateral replacement project to begin the week of September 7<sup>th</sup>, with a completion date of October 2<sup>nd</sup>. Final paving and turf restoration to be completed by October 30, 2020.

#### **2. Stanton Court/Arbor Lane -- Stanton Ct to Rosemont Dr (near Webster Ave)**

Weather permitting the anticipated project schedule is as follows:

- Work started - May 13
- Worked completed - June 26

Project Status:

Paving completed; contractor & village to monitor the progress of the restored landscaping.

### **3. Garland Street – Webster Ave to Baird St**

Weather permitting the anticipated project schedule is as follows:

- Work started – May 28
- Worked completed – June 26

Project Status:

Paving completed; contractor & village to monitor the progress of the restored landscaping.

### **4. Allouez Terrace Alley – Riverside Dr to end.**

Weather permitting the anticipated project schedule is as follows:

- Work started – May 14
- Worked completed – June 16

Project Status:

Paving completed contractor will return to install gravel shoulder.

### **5. East St Joseph Alley behind Associated Bank**

Weather permitting the anticipated project schedule is as follows:

- Work started – May 14 (asphalt removal)
- Worked completed – June 16

Project Status:

Paving completed.

### **6. Olde River Condominium Trail**

Weather permitting the anticipated project schedule is as follows:

- Work to Begin as weather permits
- Worked completed – June 16

Project Status:

Paving & shouldering completed contractor will return for turf restoration.

### **7. Longview Pond Trail Repair**

- Worked completed – June 15

### **8. Bethel Pond Project**

The anticipated project schedule is as follows:

- Work to Started – August 3
- Substantial Completion Date – October 23<sup>rd</sup>, 2020

The Village will be constructing a 1-acre regional stormwater pond located east of the Bethel Baptist Church on the south side of Kalb Street. In conjunction with the project, the Village will be installing 1350 ft of 48" Storm Sewer along the south southside of Kalb Street from Irwin Avenue east to the pond.

Project Status:

The excavation of the pond has started, it is anticipated that work on the pond will be completed by the middle of October. The installation of the pond storm sewer, inlet and outlets to begin on the 21<sup>st</sup> of September and be completed by the middle of October.

### **9. Standpipe (Water Tower) Repair Project**

Minor structural repairs to the Water Tower are anticipated to begin on the 13<sup>th</sup> of July. In general the interior and exterior repairs consist of replacement of the overflow weir box, exterior power washing, touch-up painting, improvements to the fall protection equipment, and upgrading at grade overflow pipe.

The anticipated project schedule is as follows:

- Work Started Mid - July
- Worked Completed - August 6

Project Status:

Work has been completed and we are back to normal operations.

Sincerely,



Sean Gehin, P.E.  
Director of Public Works  
Ph. 920-448-2800, Ext. 108  
Email: [seang@villageofallouez.com](mailto:seang@villageofallouez.com)



Jeff Piette  
Engineering Technician  
Ph. 920-448-2800 Ext. 122  
Email: [jeff@villageofallouez.com](mailto:jeff@villageofallouez.com)